MYSORE DIVISION:

Notification dated 20th January 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on Monday the 17th February 1936, for restoring Halehalli Hirikere Tank, Maddur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 380 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Halehalli Hirikere Tank, Maddur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Halehalli Hirikere Tank, Maddur Taluk.

No.	Description of work	Per	Rate	Quantity
	R. L. of Bund 56.00.		Rs. a. p.	
1	Clearing jungle roots, etc., grubbed up	L. S.	14 0 0	
2	Cutting grips to old bund	Grade	1 8 0	14
3	Earthworks to bund with watering and tamping	C.yd.	0 4 0	9,900
4	Do excavating foundation for core wall ..	,,	0 3 0	112
5	Clearing sand and silt in breach	,,	0 2 0	500
6	Excavation in soft rock for foundation of core wall ..	,,	0 8 0	37
	(*a*) Stone jelly concrete in foundation	C.ft.	0 3 9	596
7	Masonry core wall	,,	0 4 9	1 040
	(*a*) Puddle wall	C.yd.	0 10 0	428
8	Rough stone revetment	,,	1 12 0	1,073
	(*a*) Gravel backing to revetment	,,	0 7 0	358
9	Turfing to front and rear slope of bund	Sqr.	0 10 0	411.49
10	Providing grade stone including cutting figures and painting	Grade	2 0 0	14
11	Do Index stones	,,	0 8 0	14
12	Providing gauge stone including, cutting figures and painting	Lumpsum	15 0 0	
	(*a*) Providing B.M. stones	No.	2 8 0	2
13	Do Register No. and date stone	,,	5 0 0	1
	Construction of Sluice R. L. of 44.00.			
1	Earthwork cut open the bund	C.yd.	0 3 0	82
2	Stone jelly concrete in surki mortar	C.ft.	0 3 9	167
3	Burnt brick in surki mortar	,,	0 4 9	790
4	Plastering with surki mortar	Sqr.	3 12 0	1.38
5	Burnt stone slabs	S.ft.	0 8 0	128

Sl. No.	Description of work	Per	Rate	Quantity
			Rs. a. p.	
6	Providing and fixing Cast Iron Pipe 6" dia. including pointing	R.ft.	2 12 0	27
7	Providing and fixing plug and iron rod with locking arrangements	Lumpsum	20 0 0	
8	Earthwork refilling the sides of sluice	C.yd.	0 2 0	50
9	Gravel mixing in front slope	„	0 7 0	10
	Construction of a New Waste Weir 120 ft. long (left) R.L. 50.00.			
1	Earthwork excavation foundation and using to spoil to training bank	Cyd.	0 4 0	115
2	Do draft and approach clearing	„	0 4 0	1,389
3	Stone jelly concrete in surki mortar	C.ft.	0 3 9	396
4	Burnt brick in surki mortar	„	0 4 9	798
5	Plastering with surki mortar	Sqr.	3 12 0	8.70
6	Plastering with cement	„	8 0 0	2.72
7	Rough stone work with jelly backing	C.yd.	1 12 0	53

Notification dated 20th January 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on the 10th February 1936 for improving Yelandur-Mambally Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 245 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Yelandur-Mamballi Road" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for improving Yelandur-Mambally Road.

No.	Description of work	Per	Quantity	Rate	Cost	Total
				Rs. a. p.	Rs. a. p.	Rs. a. p.
1	Picking the road surface	S.yd.	43,560	0 0 1½		
2	Collecting, spreading and consolidating sand with an average lead of one mile	C.yds.	2,800	0 12 0		
3	Side lowering including side drains and raising sides and check drains ..	„	6,820	0 3 0		
4	Repairs to shoulder drains	..	40	25 0 0		
5	Revetments, turfing, etc., here and there	..	L.S.	150 0 0		

V. V. PATANKAR,
Executive Engineer.